MANDATORY QUALITY ASSURANCE PROVISIONS

P/N: 4026T91P01
NSN: 5307-00-151-9238
NOMEN: T64 SHOULDERED BOLT
CRITICALITY (CSI/CAI/Non-critical): CSI
DATE OF DETERMINATION: 15 MARCH 2004

APPLICABLE CLAUSES:

I. Articles to be furnished hereunder shall be manufactured, tested and inspected in accordance with drawing number **General Electric** drawing **4026T91** revision "D" or latest revision level and all details and specifications referenced therein.

II. Quality/Inspection Requirements

A. MIL-I-45208 applies or ISO 9000 equivalent.

B. First Article Testing applies. **(Government Testing)**

C. Production Lot Testing applies. **(Government Testing)**

D. Mandatory Inspection applies.

III. Supplemental Requirements

A. Additionally, paragraphs 3.1-3.5, 5.1-5.2, and 6.1-6.2 of MIL-Q-9858 or ISO 9000 equivalent applies.

B. The contractor shall include on the detailed process/operation sheets developed, a tracking method that is traceable to the contract, all manufacturing sources performing processes/operations both those performed in-house and those outsourced and a tracking method that is traceable to the contract. These sheets shall not be revised or altered after the successful completion of First Article or Production Lot Testing without approval from the ESA located at the **NADEP** Cherry Point, North Carolina **(H53ISST.6)** via the PCO. Depending upon the proposed change, a new First Article Inspection may be required.

C. The Inspection Method Sheets (IMS) which list the characteristics of each item produced under the contract shall have traceability to the raw material, casting, or forging. The tracking method used on the IMS shall have traceability to the contract. In addition, the contractor is responsible for providing completed IMS showing the actual dimensions taken for all critical characteristics.

MANDATORY QUALITY ASSURANCE PROVISIONS continued

D. Markings shall be I/A/W MIL-STD-130 latest revision, and method and location shall be I/A/W drawing.

IV. Mandatory Inspection Requirements

During production, mandatory inspection is required to be accomplished by the contractor as follows:

A. Level of Inspection (LOI).

1) Critical Characteristics: 100% inspection shall apply

2) Major and Minor Characteristics - LOI shall be I/A/W sampling plan acceptable to the QAR

B. Critical Characteristics **4026T91**:

1) **Zone D7, ⊖ .011 to .009**
2) **Zone B5, .190-32-NS per MIL-S-8879**
3) **Material: AMS 5708 per C50TF25 CL-A.**
4) **Fluorescent Penetrant Inspection per P3TF2**
5) **Harden to be Rockwell C32-42.**
6) **Zone B5 .1903 to .1898 DIA.**

C. Major and Minor Characteristics

1) Shall be defined by the contractor subject to QAR concurrence, unless defined on applicable drawings and associated specifications.

V. Unless expressly provided for elsewhere in this Clause, equipment such as fixtures, jigs, dies, patterns, templates, mylars, special tooling, test equipment, or any other manufacturing aid required for the manufacture and/or testing of the subject item(s) will not be provided by the Government and is the sole responsibility of the contractor. The foregoing applies notwithstanding any reference to such equipment or the furnishing thereof that may be contained in any drawing or referenced specification.

FIRST ARTICLE TEST REQUIREMENTS (GOVERNMENT TESTING)

P/N: 4026T91P01
NSN: 5307-00-151-9238
NOMEN: T64 SHOULDERED BOLT
CRITICALITY (CSI/CAI/Non-critical): CSI
DATE OF DETERMINATION: 15 MARCH 2004

I. First Article Inspection/Test Criteria:

The tests to be performed under the First Article approval clause of the contract are:

A. Compliance with **General Electric** drawing **4026T91 revision "D"** or latest revision level and all details and specifications referenced therein.

B. Identification: Verification and certification that the parts are identified per the requirements of **General Electric** drawing **4026T91 revision "D"** or latest revision level and all specifications referenced therein.

C. Packaging and Preservation: Verification that the parts have been packaged and preserved per the requirements of the contract.

D. Verification and certification of the overall workmanship of the First Article Sample(s).

E. Visual: Dimensional: 100% dimensional.

F. Non-Destructive Inspection: Fluorescent Penetrant Inspection per P3TF2 CL-A.

G. Fit/Form/Function: Stage Two Spacer Disk P/N 4006T69P02, stage 2 disk P/N 5007T46P02 and front shaft P/N 5007T03P02.

H. Material Analysis of the First Article Sample(s):

1) **Material: AMS 5708 per C50TF25 CL-A.**
2) **Hardness to be C32-42.**

I. Review of documentation as provided under DD 1423 requirements.

In addition to the above tests, the First Article(s) to be delivered hereunder shall also be subjected to those tests that will demonstrate that the articles comply with contract requirements. The contractor shall be responsible for providing necessary parts and repair of the First Article(s) during testing.

II. Samples to be submitted for testing:

A. Quantity **2** each.

FIRST ARTICLE TESTS REQUIREMENTS (GOVERNMENT TESTING) continued

B. Estimated Cost: POC for estimates at NADEP CP is Mr. Harold Hardison, AIR-6.1.1.1, (252) 464-7228 or hardisonHL@navair.navy.mil.

III. Special Instructions:

A. Upon successful first article inspection all processes are to be frozen.

B. **One** sample(s) will be destroyed during testing and will not be returned to the contractor. One sample(s) may be considered as production items under the contract provided the sample could be refurbished to ready for issue (RFI) condition and provided the sample has inspection approval of the cognizant QAR. Sample(s) may be shipped as production items only after all other units required under the contract have been produced and are ready for shipment.

C. Waiver of the destruction of the First Article test piece may be granted if the contractor provides a certified test coupon that is of the same material and has undergone the same special processes as the First Article test piece.

D. One sample is to be unpainted and all corrosive areas are to be coated with a light preservative on both samples.

Notification of Shipment of Material for Government Testing

A. Fourteen (14) days prior to shipment of the First Article Sample(s) the contractor shall notify the designated test facility, in writing of the anticipated shipping date, with an information copy to the PCO, ACO, and QAR. The contractor shall also arrange for preliminary inspection of test sample(s) by the CAO/QAR. The First Article Sample(s) shall be forwarded to the following First Article point of contact at the designated test facility:

Commanding Officer
Naval Air Depot
Attn: AIR-3.3.2 (Mr. Steve Lundberg)
Bldg. 159, Door R-4
Cherry Point, NC 28533-0021

B. Upon shipment of First Article Sample(s), two (2) copies of the Material Inspection and Receiving Report (DD Form 250), bearing the QAR's signature and indication of preliminary inspection, shall be forwarded to the PCO/ACO DSCR Code DSCR-KEE, and the designated test facility. In addition, the contractor must supply all detailed process/operation sheets, Inspection Method Sheets, First Article Test Report (Signed by the QAR), and all Certificates of Compliance for material (including chemical analysis), Fluorescent Penetrant Inspection and any out-sourced process conducted on the First Article Sample(s). These forms and documentation may either be placed in the shipping container with the sample(s) or sent

FIRST ARTICLE TESTS REQUIREMENTS (GOVERNMENT TESTING) continued

separately, however the envelopes shall be clearly marked, "DO NOT OPEN IN MAILROOM." These forms and documentation shall be sent to the following point of contact:

Commanding Officer
Naval Air Depot
Attn: AIR-3.3.2 (Mr. Steve Lundberg)
Bldg. 159, Door R-4
Cherry Point, NC 28533-0021

Within 120 days after receipt of the sample(s) the test site shall complete testing/evaluation and submit a copy of their test report with conclusions and recommendations to DSCR-KEE.

FIRST ARTICLE APPROVAL (GOVERNMENT TESTING)

P/N: 4026T91P01
NSN: 5307-00-151-9238
NOMEN: T64 SHOULDERED BOLT
CRITICALITY (CSI/CAI/Non-critical): CSI
DATE OF DETERMINATION: 15 MARCH 2004

APPLICABLE CLAUSES:

A. The contractor shall deliver unit(s) of lot/item within 180 calendar days from the date of this contract to the activity listed below for the purpose of partial inspection/testing and preparation of test report per the requirements specified in MIL-HDBK-831 prior to forwarding sample(s) with report to the Government designated test facility listed below:

Commanding Officer
Naval Air Depot
First Article Test – Sta. 31B
Attn: AIR-3.3.2 (252) 464-7748
Bldg. 154B Cleveland Drive
MCAS Cherry Point, NC 28533

B. The contractor shall deliver **two** unit(s) of lot/item within 180 calendar days from the date of this contract to the Government Marking of test sample(s) shipping container: "FOR FIRST ARTICLE TESTING. NOT RFI MATERIAL. DO NOT TAKE UP IN STOCK. CONTRACT NUMBER: _____ For First Article Test, the shipping documentation shall contain this contract number and the lot/item identification. The characteristics that the First Article must meet the testing requirements are specified elsewhere in this contract.

C. Within 120 calendar days after the Government testing facility receives the First Article Sample(s), the QAR's signed Material Inspection and Receiving Report, DD Form 250 and all detailed Process/Operation Sheets, Inspection Method Sheets, First Article Test Report (Signed by the QAR), and all Certificates of Compliance for material (including chemical analysis), Magnetic Particle Inspection, any out-sourced process conducted on the First Article Sample(s) and all technical data used to manufacture the First Article Sample(s), the contracting officer shall notify the contractor, in writing, of the conditional approval, approval or disapproval of the First Article. The notice of conditional approval or approval shall not relieve the contractor from complying with all requirements of the specifications and all other terms and conditions of this contract. A notice of conditional approval shall state any further action required of the contractor. A notice of disapproval shall cite reasons for the disapproval.

D. If the First Article is disapproved, the contractor, upon Government request, shall submit an additional First Article for testing. After each request, the contractor shall make any necessary changes, modification, or repairs to the First Article or select another First Article for testing. All costs related to these tests are to be borne by the contractor, including any and all costs for

FIRST ARTICLE APPROVAL (GOVERNMENT TESTING) continued

additional tests following disapproval. The contractor shall furnish any additional First Article to the Government under the terms and conditions and within the time specified by the Government. The Government shall act on this First Article within the time limit specified in paragraph B above. The Government reserves the right to require an equitable adjustment of the contract price for any extension of the delivery schedule or for any additional costs to the Government related to these tests.

E. If the contractor fails to deliver any First Article on time, or the contracting officer disapproves any First Article, the contractor shall be deemed to have failed to make delivery within the meaning of the default clause of this contract.

F. Unless otherwise provided in the contract, the contractor

1) May deliver the approved First Article as a part of the contract quantity, provided it meets all contract requirements for acceptance and was not consumed or destroyed in testing and;

2) Shall remove and dispose of any First Article from the Government test facility at the contractor's expense.

G. If the Government does not act within the time specified in paragraph B or C above, the contracting officer shall, upon timely written request from the contractor, equitably adjust under the changes clause of this contract the delivery or performance dates and/or the contract price, and any other contractual term affected by the delay.

H. The contractor is responsible for providing operating and maintenance instructions, spare parts support, and repair of the First Article during any First Article Test.

I. Before First Article approval, the acquisition of materials or components for, or the commencement of production of, the balance of the contract quantity is at the sole risk of the contractor. Before First Article approval, the costs thereof shall not be allocable to this contract for

1) progress payments, or

2) termination settlements if the contract is terminated for the convenience of the Government.

J. The contractor shall produce both the First Article and the production quantity at the same facility and shall submit a certification to this effect with each First Article and production lot.

K. The contractor shall provide specific written notification to the procuring contracting officer informing him of the shipment of any; article(s) furnished in accordance with this clause. Such notification must be addressed to the attention of the ACO with copies to DSCP and to the testing activity. Failure to provide such notification shall excuse the Government from any delay in performing First Article Testing and informing the contractor of the results thereof.

PRODUCTION LOT TESTING REQUIREMENTS (GOVERNMENT TESTING)

P/N: 4026T91P01
NSN: 5307-00-151-9238
NOMEN: T64 SHOULDERED BOLT
CRITICALITY (CSI/CAI/Non-critical): CSI
DATE OF DETERMINATION: 15 MARCH 2004

The material produced under contract shall be accepted by the cognizant CAO/QAR upon the successful completion of these requirements.

I. Production Lot Test Requirements

A. The cognizant CAO/QAR shall select the applicable number of items at random from the production lot per the ANSI/ASQC Z1.4 Sampling Procedures and Tables for Inspection by Attributes. In addition the QAR shall select the applicable number of items at random from each successive lot or portion thereof per the ANSI/ASQC Z1.4 Sampling Procedures and Tables for Inspection by Attributes.

B. Production Lot Testing to be completed during production after First Article Approval.

C. One sample submitted shall be unpainted and one sample shall be in Ready-for-Issue condition. Corrosive areas to be coated with a light preservative

D. If sample(s) are not destroyed during testing and are in RFI condition, they will be put into Defense Logistic Agency stock. All other samples will be returned to the contractor.

II. The tests to be performed under the Production Lot Sample testing provisions of the contract are:

A. Compliance with **General Electric** drawing **4026T91 revision "D"** or latest revision level and all details and specifications referenced therein.

B. Identification: Verification and certification that the parts are identified per the requirements of **General Electric** drawing **4026T91 revision "D"** or latest revision level and all details and specifications referenced therein.

C. Packaging and Preservation: Verification that the parts have been packaged and preserved per the requirements of the contract.

D. Visual: Verification and certification of the overall workmanship of the Production Lot Sample(s).

E. Dimensional: Verification and certification of 100% dimension check of finished Production Lot Sample(s).

PRODUCTION LOT TESTING REQUIREMENTS (GOVERNMENT TESTING)

F. Non-Destructive Inspection: Fluorescent Penetrant Inspection per P3TF2 CL-A

G. Fit/Form/Function: Stage Two Spacer Disk P/N 4006T69P02, stage 2 disk P/N 5007T46P02 and front shaft P/N 5007T03P02.

H. Material Analysis of the Production Lot Sample(s):

1) **Material: AMS 5708 per C50TF25 CL-A.**
2) **Hardness to be C32-42.**

A destructive material analysis can be waived ONLY if a destructive material analysis was conducted by the Engineering Support Activity (ESA), (H53ISST.6) during a successful First Article Inspection. However, all applicable material certificates of compliance will have to be provided for the production lot for verification of the material.

I. Review of documentation as provided under DD 1423 requirements.

In addition to the above tests, the Product Lot Sample(s) to be delivered hereunder shall also be subjected to those tests, which will demonstrate that the sample(s) comply with contract requirements.

III. Testing Location

A. The contractor is to ship sample(s) and all required documentation and technical data to:

Commanding Officer
Naval Air Depot
First Article Test – Sta. 31B
Attn: AIR-3.3.2 (252) 464-7748
Bldg. 154B Cleveland Drive
MCAS Cherry Point, NC 28533

B. The shipping container marking: "FOR PRODUCTION LOT TESTING. NON RFI MATERIAL. DO NOT TAKE UP IN STOCK. CONTRACT NUMBER_____. "

Within fifteen (15) days of completion of Production Lot Testing the CAO/QAR shall prepare and submit two (2) copies of their test report with conclusions and recommendations to the Contracting Officer.

Shipment and Distribution of Sample(s):

A. Fourteen (14) days prior to shipment of Production Lot Sample(s) the contractor shall notify the designated test facility, in writing of the anticipated shipping date, with an information copy to the PCO, ACO and the QAR. The contractor shall also arrange for preliminary inspection of test samples by the CAO/QAR.

PRODUCTION LOT TESTING REQUIREMENTS (GOVERNMENT TESTING)

B. Upon shipment of the Production Lot Sample(s), two (2) copies of the Material Inspection and Receiving Report (DD Form 250), bearing the QAR's signature and indication of preliminary inspection, shall be forwarded to the PCO/ACO DSCR (Code DSCR-KEE), and the testing facility. In addition, the contractor shall provide all detailed Process/Operation Sheets, Inspection Method Sheets, First Article Test Report (Signed by the QAR), and all Certificates of Compliance for material (including chemical analysis), Fluorescent Penetrant Inspection, any out-sourced process conducted on the Production Lot Sample(s) and all technical data used to manufacture the Production Lot Sample(s) to the testing facility. The envelopes shall be clearly marked, "DO NOT OPEN IN MAILROOM".

C. Production Lot Sample(s) may be considered as production items under the contract provided the sample(s) can be refurbished to Ready for Issue (RFI) condition and provided sample(s) have inspection approval from the cognizant DCMAO and the ESA engineer (**H53ISST.6**). Sample(s) may be shipped as production items ONLY after all other units required under contract have been produced and are ready for shipment.

D. Sample(s) will be returned to the contractor. The contractor must provide material disposition instructions to:

Commanding Officer
Naval Air Depot
First Article Test – Sta. 31B
Attn: AIR-3.3.2 (252) 464-7748
Bldg. 154B Cleveland Drive
MCAS Cherry Point, NC 28533

E. The designated test facility and the contracting officer shall be notified as to all shipping data applicable to the sample(s), such as bill of lading number, method of shipment, etc. within fourteen (14) days prior to shipping.

PRODUCTION LOT TESTING APPROVAL (GOVERNMENT TESTING)

P/N: 4026T91P01
NSN: 5307-00-151-9238
NOMEN: T64 SHOULDERED BOLT
CRITICALITY (CSI/CAI/Non-critical): CSI
DATE OF DETERMINATION: 15 MARCH 2004

A. The Production Lot Samples shall be:

1. Selected at random by the cognizant government QAR. Such samples shall be submitted via the cognizant government inspector, and all transportation charges prepaid by the contractor to:

Commanding Officer
Naval Air Depot
First Article Test – Sta. 31B
Attn: AIR-3.3.2 (252) 464-7748
Bldg. 154B Cleveland Drive
MCAS Cherry Point, NC 28533

2. The samples shipping container and samples shall be identified by contract number, lot number and be clearly marked as follows:

PRODUCTION LOT TEST SAMPLES
NON-RFI MATERIAL
DO NOT TAKE UP IN STOCK

B. Such samples shall be delivered to the testing facility in sufficient time prior to the delivery date of the production articles to allow a 90 day period for testing and written notification by the contracting officer of the approval or disapproval of the samples. Within 120 days of the receipt of the samples, the testing facility shall notify the contracting officer, PCO/ACO of the results of the testing, together with the recommendation for approval or disapproval.

C. In the event the contractor does not receive written notification of approval or disapproval of the samples for a particular lot within 120 days from their submission for such testing, the contract delivery schedule shall be equitably adjusted as necessary.

D. If the contractor fails to deliver any Production Lot Samples for testing within the time or times specified, or if the contracting officer disapproves any Production Lot Samples, the contractor shall be deemed to have failed to make delivery within the meaning of the default clause of this contract, and this contract shall be subject to termination for default.

E. In order for a Production Lot to be acceptable, all samples representative of the lot must pass all the contract requirements. In the event a sample fails to pass such requirements, the lot will

PRODUCTION LOT TESTING APPROVAL (GOVERNMENT TESTING) continued

be rejected. In such event, the government may, at its option and at no additional cost to the government, (I) terminated all or any portion of this contract for default, (II) require the manufacture of a new Production Lot, or a rework of the rejected Production Lot if the means and procedures by the contractor for rework are acceptable to the government, or (III) require the submission of additional samples for test. The foregoing procedures shall apply to new or reworked Production Lots in the same way as they did to the original Production Lot.

F. For each additional sample or each resubmission of a modified sample which the contractor is required to submit for approval hereunder as a result of a failure of a previous sample to conform to the requirements of the specification, the contractor shall pay to the government the costs of reinspection, examination and retesting and the contractor and his sureties (if any) shall be liable for the amount of such costs.

G. The contractor must provide material disposition instructions to the First Article Coordinator at the POC and address below for the return of the production lot samples.

Commanding Officer
Naval Air Depot
First Article Test – Sta. 31B
Attn: AIR-3.3.2 (252) 464-7748
Bldg. 154B Cleveland Drive
MCAS Cherry Point, NC 28533

H. Nothing contained in the foregoing provisions of this clause, and not action of the government in accordance herewith, shall in any way prejudice the right of the government under this clause of this contract entitled default.

CONTRACT DATA REQUIREMENTS LIST

Form Approved
OMB No. 0704-0188

The public reporting burden for this collection of information is estimated to average 440 hours per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing the burden, to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports (0704-0188), 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number. Please DO NOT RETURN your form to the above address. Send completed form to the Government Issuing Contracting Officer for the Contract/PR No. listed in Block E.

A. CONTRACT LINE ITEM NO.	B. EXHIBIT	C. CATEGORY: TDP X TM ____ OTHER ____
D. SYSTEM/ITEM: 5307-00-151-9238	E. CONTRACT/PR NO.	F. CONTRACTOR

1. DATA ITEM NO. 0001 | **2. TITLE OF DATA ITEM** CERTIFICATION DATA REPORTS | **3. SUBTITLE** COMPLETE PROCESS/OPERATION SHEET

4. AUTHORITY (Data Acquisition Document No.) DI-MISC-80678/T1 | **5. CONTRACT REFERENCE** | **6. REQUIRING OFFICE** DSC PHILADELPHIA

7. DD 250 REQ LT | **8. APP CODE** A | **9. DIST STATEMENT REQUIRED** | **10. FREQUENCY** AS REQUIRED | **11. AS OF DATE** | **12. DATE OF FIRST SUBMISSION** BLOCK 16* | **13. DATE OF SUBSEQUENT SUBMISSION** BLOCK 16**

16. REMARKS
PARA. 10.1, 10.2, 10.2.1, 10.2.2, 10.2.4, 10.5 APPLY//*UPON SUBMISSION OF FIRST ARTICLE TESTING//**IF THE PROCESS/OPERATIONS CHANGES AFTER APPROVAL OF FIRST ARTICLE TEST

14. DISTRIBUTION

a. ADDRESSEE	b. COPIES Draft	Final Reg	Final Repro
NAVAIRCP 3.3.2	0	1	0
DSCP	0	1	0
CAO	0	1	0
15. TOTAL →	0	3	0

17. PRICE GROUP
18. ESTIMATED TOTAL PRICE

1. DATA ITEM NO. 0002 | **2. TITLE OF DATA ITEM** CERTIFICATION DATA/ REPORT | **3. SUBTITLE** COMPLETE INSPECTION METHOD SHTS

4. AUTHORITY (Data Acquisition Document No.) DI-MISC-80678/T2 | **5. CONTRACT REFERENCE** | **6. REQUIRING OFFICE** DSC PHILADELPHIA

7. DD 250 REQ LT | **8. APP CODE** A | **9. DIST STATEMENT REQUIRED** | **10. FREQUENCY** AS REQUIRED | **11. AS OF DATE** | **12. DATE OF FIRST SUBMISSION** BLOCK 16* | **13. DATE OF SUBSEQUENT SUBMISSION** BLOCK 16**

16. REMARKS
PARA. 10.1, 10.2, 10.2.1, 10.2.2, 10.2.4, 10.5 APPLY//*UPON SUBMISSION OF FIRST ARTICLE TESTING//**SUBSEQUENT SUBMISSION TO BE MADE UPON COMPLETION OF CONTRACT.

14. DISTRIBUTION

a. ADDRESSEE	b. COPIES Draft	Final Reg	Final Repro
NAVAIRCP 3.3.2	0	1	0
DSCP	0	1	0
CAO	0	1	0
15. TOTAL →	0	3	0

17. PRICE GROUP
18. ESTIMATED TOTAL PRICE

1. DATA ITEM NO. 0003 | **2. TITLE OF DATA ITEM** REQUEST FOR DEVIATION | **3. SUBTITLE**

4. AUTHORITY (Data Acquisition Document No.) DI-CMAN-80640C | **5. CONTRACT REFERENCE** | **6. REQUIRING OFFICE** DSC PHILADELPHIA

7. DD 250 REQ LT | **8. APP CODE** | **9. DIST STATEMENT REQUIRED** | **10. FREQUENCY** AS REQUIRED | **11. AS OF DATE** | **12. DATE OF FIRST SUBMISSION** BLOCK 16 | **13. DATE OF SUBSEQUENT SUBMISSION**

16. REMARKS
ORIGINAL AND TWO COPIES

14. DISTRIBUTION

a. ADDRESSEE	b. COPIES Draft	Final Reg	Final Repro
CAO	0	1	0
NAVAIRCP 3.3.2	0	1	0
DSCP	0	1	0
15. TOTAL →	0	3	0

17. PRICE GROUP
18. ESTIMATED TOTAL PRICE

1. DATA ITEM NO. | **2. TITLE OF DATA ITEM** | **3. SUBTITLE**

4. AUTHORITY (Data Acquisition Document No.) | **5. CONTRACT REFERENCE** | **6. REQUIRING OFFICE**

7. DD 250 REQ | **8. APP CODE** | **9. DIST STATEMENT REQUIRED** | **10. FREQUENCY** | **11. AS OF DATE** | **12. DATE OF FIRST SUBMISSION** | **13. DATE OF SUBSEQUENT SUBMISSION**

16. REMARKS

14. DISTRIBUTION

a. ADDRESSEE	b. COPIES Draft	Final Reg	Final Repro
15. TOTAL →			

17. PRICE GROUP
18. ESTIMATED TOTAL PRICE

G. PREPARED BY	H. DATE	I. APPROVED BY	J. DATE
Timothy L. Bennett	11 May 05		8-12-05

CONTRACT DATA REQUIREMENTS LIST

Form Approved
CMB No. 0704-0188

Public reporting burden for this collection of information is estimated to average 110 hours per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden to Department of Defense, Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 222202-2302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503. Please DO NOT RETURN your form to either of these addresses. Send completed form to the Government Issuing Contracting Officer for the Contract. PR No. listed in Block E.

A. Contract Line Item No.	B. Exhibit	C. Category ENGINEERING
D. System/Item **5307-00-151-9238**	E. Contract/PR NO.	F. Contractor
1. Data Item No. 0004	2. Title of Data Item: CERTIFICATION/DATA REPORTS	3. Subtitle: CERTIFICATION/ DATA REPORTS
4. Authority (Data Acquisition Document No.) DI-MISC-80678/T3	5. Contract Reference	6. Requiring Office DSC PHILADELPHIA

7. DD 250 Req LT	9. Dist Statement Required	10. Frequency AS REQUIRED	12. Date of First Submission BLOCK 16	14. Distribution			
8. APP Code A		11. As of Date	13. Date of Subsequent Submission BLOCK 16	a. Addressee	b. Copies		
					Draft	Final	
						Reg	Repro

16. REMARKS

PARA. 10.1, 10.2.1, 10.2.2, 10.2.4, 10.5 APPLY

BLOCK 3:

SEPARATE REPORTS SHALL BE PROVIDED FOR THE BELOW LISTED SUBTITLES AND SHALL INCLUDE CERTIFICATIONS THAT ALL VENDORS PERFORMING THESE PROCESSES ARE PRIME (OEM) APPROVED SOURCES. IN THE CASE WHERE OTHER THAN THE OEM'S SPECIFICATIONS ARE TO BE UTILIZED, SEPARATE CERTIFICATIONS ARE REQUIRED.

1. MATERIAL CERTIFICATIONS AND ANALYSIS DOCUMENTATION FOR:

a. Verify and certify the material composition of AMS 5708 per C50TF25 CL-A.

b. Verify and certify the material composition of hardness to be C32-42.

2. INSPECTION CERTIFICATIONS FOR:

a. Fluorescent Penetrant Inspection per P3TF2 CL-A.

BLOCK 12:

* UPON SUBMITTAL OF FIRST ARTICLE TESTING SAMPLE(S)

CONTRACTOR SITE: FOR REVIEW

GOVERNMENT SITE: AS DELIVERABLE

BLOCK 13:

**UPON SUBMITTAL OF PRODUCTION LOT INSPECTION SAMPLE(S)

CONTRACTOR SITE: FOR REVIEW

GOVERNMENT SITE: AS DELIVERABLE

a. Addressee	Draft	Final Reg	Final Repro
NAVAIR CP AIR- 3.3.2	0	1	0
DCMC/QAR	0	1	0
DSCP	0	1	0
15. TOTAL	0	3	0

G. PREPARED BY	H. DATE	I. APPROVED BY	J. DATE
Timothy L. Bennett *Timothy L Bennett*	12 May 2005	*Christopher A Lucas*	8-12-05